

## Dismantle, assembly and installation plans

for the ALBA II upgrade

F.Fernandez and M.Pont

3rd Workshop on Particle Accelerator Upgrade - Removal and Installation 18-20 March 2024. Trieste



- ALBA synchrotron light source in Operation since 2012
  - Top-up @250mA
  - 13 Beamlines
- Upgrade to
  - Improve brightness and coherence of the beam
  - Add two new long beamlines
  - Enhance data capabilities
- Dark period 2030-2031

## **Upgrade considerations**

- Storage Ring Magnets, Vacuum, Diagnostics and Pulsed elements upgraded
- Insertion Devices, Radiofrequency, Front Ends Injector and main services kept
- 3<sup>rd</sup> order harmonic cavities and Solid State Amplifiers for the 500MHz RF
- Existing ID&BL positions maintained
- RF changes location in tunnel and Service Area
- SR MA tested and mounted on girders in advance. VC assembled by sectors in advance (NEG ex-situ activation)



- Required spaces to store, test and assembly have been estimated
- Use of onsite areas
- A temporary storage area is required to store the new SR pre&post assembly as well as the present SR

	MA	GIRDERS	VC	PS
Storage	300m <sup>2</sup>	900m <sup>2</sup>	60m <sup>2</sup>	300m <sup>2</sup>
Testing	65m <sup>2</sup>		$220m^2$	150m <sup>2</sup>
Assembly	200m <sup>2</sup>		22011-	
Storage Ring Assembled	800m <sup>2</sup>		50m <sup>2</sup>	300m <sup>2</sup>





 200m<sup>2</sup> are being considered to assembly&test 2 girders with their supports&mechanics and assembly and prealign the magnets on the girders







- A large reorganization of the Service Area will we needed
  - The RF plants&cavities change position
  - The number of racks will increase

	ALBA	ALBA II
Injector & others	155	187
SR_PC	58	128
SR_VC	34	34
SR_RF	19	50
SR_FE	20	36





## **Thanks for your attention**